



Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Ackerly	CD	\$350,000	229	123	53.71	Contractor shall replace 1430 l.f. of undersized water line with 6" PVC water line, related valves and fittings, and install an arsenic removal unit, pump, piping, electrical and controls, and a building for the system located on 6th and Avenue A. Line replacement shall take place on 1st street and Avenues E and G.
Agua Dulce	CD	\$300,000	669	384	57.40	Contractor shall address infiltration by installing 2 new oxidation ditch horizontal aerators, 2 clarifier scraper assemblies, 2 clarifier skirts, and 1 stationary dedicated 45kW emergency power generator at the treatment facility. Construction shall take place at the treatment plant located at the intersection of State Highway 44 and State Highway 70.
Alvarado	CD	\$350,000	3,086	1,844	59.75	Contractor shall install 3165 lf of 12" water main, 175 lf of 6" water main, 6 fire hydrants, gate valves and valve boxes, and replace pavement along Sunflower Lane and Tanglewood, providing a direct water supply and additional pressure to the northeast portion of the city addressing a TCEQ Agreed Order.
Ames	CD	\$350,000	1,184	838	70.78	Contractor shall perform citywide water system improvements to address low water pressure and address inadequate water system storage capacity. Construction shall consist of installing 1,000 l.f. of 6" water line and 1 50,000 gal. ground water storage tank. Construction shall take place at the Donnato Street Water Plant.
Angelina County	CD	\$250,000	481	316	65.70	Contractor shall perform water system improvements on behalf of the Prairie Grove WSC. Construction shall consist of installing 11,220 LF of water main, replacing remaining water lines with new 4" water main, and related appurtenances. Construction shall take place along FM 1818 beginning at the FM 1818 Water Plant and along FM 1818.
Bailey County	CD	\$250,000	48	26	54.17	Contractor shall construct a new 12' by 100' elevated water storage tank including piping and controls. Construction shall take place 1.8 miles south of FM 596 and FM 54.
Balmorhea	CD	\$350,000	542	370	68.27	Contractor shall remove silt from the reservoir and rehabilitate the original intake structure. Construction shall take place at the Big Aguja Spring west of city. Project shall benefit entire city.
Bangs	CD	\$250,000	1,553	835	53.77	Contractor shall install a new sludge processing system, and replace two existing rotors in the oxidation ditch.
Beeville	CD	\$500,000	1,015	624	61.48	Contractor shall construct pressure, supply and storage facilities to provide metered water to the Blueberry Hill Water Works. Contractor shall construct 1 pump station, 1 wholesale meter, 3,500 lf of 12", 8", and 6" water line, 3 fire hydrants, and appurtenances. Construction shall take place in the Blueberry Hill colonia area.
Bellevue	CD	\$250,000	340	241	70.88	Contractor shall improve the existing waste water treatment plant by removing excess sludge from the race track and primary stabilization pond, adding an additional stabilization pond and installing a new aeration system.
Blue Ridge	CD	\$350,000	661	385	58.25	Contractor shall install 1000 lf of 2" force main, 2 manholes, 1100 lf of 6" sewer line, a grinder pump lift station and eliminate two existing lift stations along Highway 78 providing new sewer service to 3 households on Lamm Street. Contractor shall also replace 1180 lf of 8" water main, 260 lf of 4" water lines, 10 valves, 2 new fire hydrants, bore and casing, and conduct pavement repairs in the Hwy 78, Main Street, FM 545 area.
Bogata	CD	\$250,000	1,326	678	51.13	Contractor shall replace defective clay sewer main and brick manholes through the installation of approximately 4,100 l.f. of 12" PVC sewer main, 11 concrete manholes and the abandonment of the old sewer main. Construction shall take place on the sewer plant road from the WWTP to U.S. 271.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Bonham	CD	\$125,000	6,785	3,511	51.75	Contractor shall construct four soccer fields for children, an access road, parking area, culverts, field irrigation system, seeding, bleachers, goals and markings. Construction shall take place near 12th Street and CR 1540.
Brady	CD	\$200,000	1,664	1,048	62.98	Contractor shall replace an undersized and dilapidated 100,000 gallon ground storage tank north of South Avenue and Melwood.
Bremond	CD	\$250,000	801	450	56.18	Contractor shall replace deteriorated cast iron water mains to ensure a reliable water supply. Construction shall include the installation of 3,380 l.f. 8" & 6" waterline, 5 hydrants, valves, service reconections, and associated pavement repairs. Construction shall take place near Main and Denton Streets.
Brenham	CD	\$250,000	1,671	1,159	69.36	Contractor shall replace one deteriorated lift station to eliminated overflows and bring the system up to code. Construction shall include one new lift station with submersible pump, electrical controls and demolition of existing lift station. Construction shall take place in Henderson Park on the city's north side.
Brewster County	CD	\$234,859	242	205	84.71	Contractor shall provide water system improvements to the Study Butte Water Supply Corporation. Contractor shall construct 2 65,000 gallon elevated ground storage tanks at Study Butte WSC water plant in Terlingua.
Broadus	CD	\$250,000	189	109	57.67	Contractor shall install 8,750 LF of 4", 3", and 2" water main, 200 lf of 12" steel casing & boring, 6 interconnects, 2,400 lf of water service line, 250 SY of pavement repair, and related appurtenances. Construction shall take place along Jackson Hill Tower Road, Shippy Road, Sheffield Road, Colwell Circle, and SH 147.
Burkburnett	CD	\$250,000	126	100	79.37	Contractor shall install 5,149 of 6" PVC water line and install 8 new fire hydrants resolving the issues of low water supply and, of fire protection and non conformance to TCEQ rules in the northeast area of Burkburnett.
Cameron	CD	\$250,000	5,534	2,992	54.07	Contractor shall address TCEQ flow and pressure requirements by replacing approximately 1,800 lf of deteriorated water line and replacing a failing backwash pump at the water treatment plant. Construction shall take place at and around the city's water treatment plant on East Gillis Street.
Cameron County	CD	\$287,597	562	428	76.16	Contractor shall install approximately 2,3400 lf of 8" and 6" waterline, boring, connections, appurtenances and driveway repair, to increase water pressure in Laguna Heights. Contractor shall install approximately 5,400 lf of 8" and 4" waterline, connections and appurtenances providing first-time water service to the Hoeing Road Area and Hatchett Road Area colonias.
Campbell	CD	\$263,100	469	422	89.98	Contractor shall modify the wastewater treatment plant in order to increase treatment capacity and prevent TCEQ violations. Construction includes the following modifications: lift station expansion, sludge disposal expansion, and aeration system reconstruction. Construction will take place at the existing WWTP.
Caney City	CD	\$250,000	56	45	80.36	Contractor shall resurface approximately 2,050 l.f. of roadway and perform related activities for all or portions of McCalister Rd, Wingham Rd, Benjamin Rd, James Rd, and St Paul Rd.
Canyon	CD	\$250,000	167	116	69.46	Contractor shall replace undersized cast iron water line to improve pressure. Construction shall include the installation of 4,200 l.f. of 2" and 8" water line, service connections and all necessary appurtenances. Construction shall take place on 1st through 4th avenues.
Charlotte	CD	\$250,000	1,636	938	57.33	Contractor shall install 3,630 lf of 6" water line, 120 lf of bore and jack with 12" casing and 6" water line, valve gates, 6 fire hydrants, fittings and reconections, and cut and patch 3,600 lf of trench. Construction shall take place on Madero Ave., San Antonio Ave., St. Louis Ave., Rodriguez Ave., McKinnen Ave. and Walker Ave.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Chico	CD	\$350,000	950	505	53.16	Contractor shall replace two 100 yr old elevated water storage tanks with a new 150,000 gallon elevated water storage tank located at the N. Mount Street tank site.
Christine	CD	\$250,000	491	297	60.49	Contractor shall install 7,721 lf of 6" water line, 100 lf of bore and jack with 12" steel casing and 6" water line, gate valves, 10 fire hydrants, reconstructions, fittings cut and patch and trench safety. Construction shall take place on Thirteenth St., Avenue I, Avenue J., Sixth St., and Avenue F.
Claude	CD	\$250,000	676	420	62.13	Contractor shall replace undersized deteriorated cast iron water lines and loop the system to improve pressure. Construction shall include 7,820 l.f. of 2", 4", 6" and 8" line, service connections and all necessary appurtenances. Construction shall take place on High, Tenth, Cherry and Eighth streets.
Cleveland	CD	\$350,000	7,495	5,299	70.70	Contractor shall address TCEQ violations by replacing a corroded ground storage tank. Construction shall consist of installing a 500,000 gallon ground water storage tank, and shall take place at the East Water Plant 3, located at 25508 SH 321.
Clint	CD	\$234,859	242	205	84.71	Contractor shall provide water system improvements to the city. Construction shall be a 1800 lf of 8" water distribution line and 2 fire hydrants along Lawson Street from Langford Street to Clint Lateral Canal.
Collinsville	CD	\$125,000	150	85	56.67	Contractor shall reconstruct approximately 3,975 lf of West Hughes Street using base restabilization and single course treatment.
Colmesneil	CD	\$250,000	622	351	56.43	Contractor shall remove existing aeration piping manifolding and headers, install 2 floating surface aerators, replace blower units, and construct a new lift station. Construction shall take place at the Wastewater Treatment Plant in the northwestern and south-central areas of town.
Columbus	CD	\$350,000	3,499	1,844	52.70	Contractor shall make water system improvements to alleviate strain on the City's water supply. Construction shall consist of constructing a new water well and installing 300 l.f. of 8" discharge piping. Construction shall take place at the intersection of Business Highway 71 and Harbert St.
Coolidge	CD	\$250,000	852	494	57.98	Contractor shall remove accumulated sludge and silt from Pond 2, excavate approximately 2,000 CY of sludge, silt and dirt to enlarge Pond 3 and install approximately 1300 CY of clay liner in Pond 3. Project, located northeast of FM Roads 73 and 1951, will include necessary bypass pumping and silt fence.
Copperas Cove	CD	\$250,000	117	103	88.03	Contractor shall address water loss and pressure concerns by replacing water main lines. Construction shall consist of installing approximately 1800 linear feet of 6" water line, 2 fire hydrants, and associated appurtenances. Construction shall take place in the central sector of the city.
Corsicana	CD	\$350,000	100	79	79.00	Contractor shall install 1650 lf of 30" sewer line and 2 60" manholes replacing asbestos concrete sewer line and disintegrating, brick manholes in a central target area around Oaklawn Drive.
Crockett	CD	\$250,000	5,113	3,332	65.17	Contractor shall install 1,540 LF of 18" and 24" sanitary sewer line, 520 LF of pipe bursting, and 7 new manholes. Contractor shall also perform 50 LF of street repair and reconnect 6 sanitary sewer services. Construction shall take place on 2nd street and cross country to Navarro lane toward the Northside Wastewater Treatment Plant.
Cuero	CD	\$250,000	141	120	85.11	Contractor shall make water and sewer system improvements by replacing deteriorated water and sewer mains. Construction shall consist of installing 3,150 lf of 8" sewer main, 7 fire hydrants, gate valves and tie-ins, 2,600 l.f. of 8" and 10" sewer line, 11 manholes and appurtenances. Construction shall take place on Evers, Woodworth and Nash Streets.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Cuney	CD	\$250,000	151	96	63.58	Contractor shall construct a community center consisting of an approximately 3,200 s.f. metal exterior building, site work, foundation, and associated interior construction and utilities. Construction shall take place on unimproved land at the southeast corner of State Hwy 175 and CR 3326.
Dayton	CD	\$350,000	103	79	76.70	Contractor shall make water system improvements to provide first-time water service to 27 households. Construction shall consist of installing 4,580 l.f. of 12", 8", and 6" water line, gate valves, 9 fire hydrants, and 2,300 l.f. of service line. Construction shall take place on CR 606, PR 6063, PR 6065, and CR 607.
Dilley	CD	\$250,000	2,882	1,964	68.15	Contractor shall install 35 6", 8", and 12" insertion valves in water mains located throughout the City.
Dimmitt	CD	\$250,000	2,362	1,421	60.16	Contractor shall rehabilitate its ground storage tank to bring it back into TCEQ compliance. Construction shall include the cleaning, refurbishing, repainting, and installing a new top. Construction shall take place at the storage tank site located at Stinson and 5th.
Eagle Pass	CD	\$600,516	199	189	94.97	Contractor shall replace 7 street culverts along the City's main arroyo from Memorial Drive to Ferry Street.
Earth	CD	\$250,000	1,125	577	51.29	Contractor shall replace deteriorated wastewater clarifier/digester unit to bring its system up to TCEQ standards. Construction shall include repairs to clarifier, sludge removal and all necessary appurtenances. Construction shall take place off of South Grape and South Elm.
East Bernard	CD	\$350,000	116	114	98.28	Contractor shall address water pressure and fire protection issues for the Amlanco area. Construction shall consist of installing 6,900 l.f. of 8" and 6" PVC water lines, 14 fire hydrants, 7,400 l.f. of 1" service lines, and appurtenances. Construction shall take place on Old Wharton Rd., FM 1164, Michael St. and Terry St.
Easton	CD	\$250,000	617	340	55.11	Contractor shall make park improvements by installing a parking lot, restrooms, septic system, playground equipment, and associated appurtenances at the city park located on the south side of Curtis Street near downtown.
Escobares	CD	\$420,000	1,835	1,431	77.98	Contractor shall construct a new 2,931 sf fire station to house existing equipment. Construction shall also include a concrete driveway and parking lot, a built up metal roof, office space and showers. The new fire station shall be located at the city hall complex on Old US Hwy 83 and Victors Rd.
Falfurrias	CD	\$300,000	5,241	3,530	67.35	Contractor shall, on behalf of Falfurrias Utility Board, rehabilitate 2 existing clarifier units, install new clarifier skimmer equipment in one unit and related electrical, controls and piping at the sewer treatment plant. Construction shall take place at the sewer plant located at FM 754 and CR 404.
Flatonia	CD	\$250,000	1,309	780	59.59	Contractor shall replace deteriorated cement sewer lines. Construction shall consist of installing 1,700 LF of 4" and 8" sewer lines, 6 manholes, and reconnections along N. LaGrange Ave., Farres Ave., and S. Colorado Ave. Contractor shall also replace deteriorated cement water lines by installing 2,175 LF of 8" water line, 3 fire hydrants, boring, gate valves, and reconnections along 9th Street, E. Mulberry, and N. Mesquite Ave.
Floydada	CD	\$250,000	3,689	1,980	53.67	Contractor shall replace deteriorated pump station to bring its system up to TCEQ standards and ensure a reliable water source. Construction shall include the installation of two 75-hp services pumps, booster pump station building, controls and all necessary appurtenances. Construction shall take place on HWY 62 and HWY 207.
Forsan	CD	\$350,000	160	88	55.00	Contractor shall replace old, undersized, and deteriorated water lines with approximately 8500 lf of 6" and 4" PVC C900 water lines, gate valves & boxes, valves, meter replacements and reconnections, and pavement patching. Construction shall take place primarily on Avenues A, B, Rex and H, and 7th Streets.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Franklin	CD	\$250,000	1,299	768	59.12	Contractor shall rehabilitate the existing 100,000 gallon elevated water storage tank to meet TCEQ standards. Construction shall include new exterior/interior coatings, piping, electrical and all necessary appurtenances. Construction shall take place at the intersection of W. Englewood and N. Center Streets.
Frio County	CD	\$250,000	332	255	76.81	Contractor shall install 6,500 lf 8" and 6" PVC line, 800 lf of 3/4" service line and 5 fire hydrants, and cut and patch approximately 400 sy of existing pavement. Construction shall take place along Rusty Furnace Rd. and Justin Rd. in the Hilltop Colonia near the city of Dilley.
Frost	CD	\$162,500	568	363	63.91	Contractor shall reconstruct the existing elevated water storage tank on Tower Street by overhauling the exterior and the interior. Contractor shall also reduce inflow and infiltration by replacing 18 manholes throughout the city's sewer system.
Garrison	CD	\$250,000	791	472	59.67	Contractor shall install 760 LF of 8" sewer main, 200 LF of steel bore casing, 16 manholes, 6 service transfers, 400 SY of pavement repair, and related appurtenances. Construction take place on US Hwy 59 from Ceder Street to Henning Road.
Gatesville	CD	\$250,000	3,087	1,578	51.12	Contractor shall rehabilitate an existing elevated water storage tank to extend the useful life of the tank. Construction shall consist of structural improvements, pit welds, material testing, and painting of the interior and exterior of the tank. Construction shall take place at the water storage tank on 23rd Street.
Gilmer	CD	\$250,000	267	224	83.90	Contractor shall make surface and road base improvements by paving approximately 1 mile of deteriorated streets. Construction shall take place on Tobe St, Cypress St, Bradford St, Warren St, and Kaufman St.
Glen Rose	CD	\$250,000	292	292	100.00	Contractor shall replace sewer service lines (yardline replacement) for 115 households city-wide.
Godley	CD	\$256,050	395	208	52.66	Contractor shall eliminate inflow and infiltration problems by upgrading 5700 LF of 6" sewer mains and 40 manholes throughout the city.
Goliad	CD	\$250,000	55	30	54.55	Contractor shall replace old deteriorated sewer pipe to eliminate stoppages and I/I problems. Construction shall consist of installing 2,425 lf of 8" sewer line, 10 manholes, and service reconnections. Construction shall take place between Fannin and Pearl and Washington and Commercial streets.
Gregory	CD	\$300,000	2,297	1,296	56.42	Contractor shall install a new 250,000 gallon ground storage tank with related piping and remove and dispose of its existing ground storage tank located at the water plant site at US Highway 181 and State Highway 35.
Hallettsville	CD	\$250,000	94	53	56.38	Contractor shall make sewer system improvements to address undersized sewer lines and I/I problems. Construction shall consist of installing of 3,060 lf of 6" and 8" sewer line, 10 manholes, reconnections and trench safety. Construction shall take place on S. Dowling, Crawford, and S. Glendale streets.
Hamilton	CD	\$250,000	296	174	58.78	Contractor shall address water flow and pressure concerns by replacing deteriorated distribution lines. Construction shall consist of installing 3,750 lf of water line, 4 fire hydrants, and necessary appurtenances. Construction shall take place in the northwest area of the city.
Harrison County	CD	\$250,000	480	283	58.96	Contractor shall make water system improvements on behalf of the Talley WSC. Construction shall consist of drilling a 100 gpm water well, installing 4,000 lf of 4" water main, gate valves, tie-ins to existing raw water main, and associated appurtenances, Construction shall take place west of Pump Station #3 in central Harrison County.
Hempstead	CD	\$350,000	4,461	2,975	66.69	Contractor shall perform sewer system improvements to alleviate sewer backups and bypasses. Construction shall consist of rehabilitating 2,825 l.f. of 8" and 10" sewer line and 16 manholes, as well as related street repairs. Construction shall take place on Rice, 12th, 18th, 20th, and Shepard streets.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Hereford	CD	\$250,000	1,633	976	59.77	Contractor shall replace deteriorated sewer lines to address TCEQ regulations and current demands. Construction shall include the installation of 3,250 l.f. of 6" sewer line, 6 manholes, service connections and all necessary appurtenances. Construction shall take place on Schley, McKinley, Lee, Miles, Ross and Jackson.
Hondo	CD	\$250,000	91	65	71.43	Contractor shall replace deteriorated clay sewer lines. Construction shall consist of 1,700 LF of 8" to 10" sewer lines, 6 manholes, reconnections and street repairs. Construction shall take place on Avenue A, Avenue B, and 15th Street.
Hubbard	CD	\$250,000	1,680	885	52.68	Contractor shall address TCEQ notice of enforcement through the installation of five (5) pressure data recorders, one computer system for downloading readings, one duplicate water plant control panel, modify the existing generator fuel storage and create an emergency response plan related to the water treatment plant located on N. Magnolia Ave. at S. First St.
Hunt County	CD	\$350,000	2,135	1,108	51.90	Contractor shall construct a 150,000 gallon elevated water storage tank with transmission line in the community of Fairlie.
Jacksboro	CD	\$250,000	78	60	76.92	Contractor shall upgrade aged and cracked sewer pipe with 2150 LF of 10" sewer line, and conduct driveway and street repair along Bowie, East Jasper, North Knox, and West Live Oak streets.
Jasper	CD	\$250,000	1,482	962	64.91	Contractor shall rehabilitate lift station #30 at MLK Drive, #32 at Newton Street, and #19 at Palmetto Street, and 17 manholes in the East Houston Street and Hall Street area of the city.
Jasper County	CD	\$250,000	77	77	100.00	Contractor shall install 30 on-site sewer systems for low to moderate income households that do not comply with TCEQ requirements in unincorporated areas throughout Jasper County.
Jeff Davis County	CD	\$234,859	835	598	71.62	The county shall provide water system improvements to the Fort Davis Water Supply Corporation. Contractor shall construct a 80,000 gallon ground storage tank. Construction shall take place at 601 Urquhart, Fort Davis.
Jefferson	CD	\$250,000	867	457	52.71	Contractor shall demolish and clear 41 vacant and dilapidated structures in the western and southern portions of the city.
Karnes City	CD	\$250,000	465	333	71.61	Contractor shall install 6,000 lf of 6" and 8" water line, 4 fire hydrants, 32 service connections, and related appurtenances. Construction shall take place on Riddleville St, the alley between Riddleville and Pleasant, Helena St, the alley between Park and Dawson, Milam St, and Runge St.
Kendall County	CD	\$250,000	2,310	1,623	70.26	Contractor shall install 1,300 lf of 15" PVC line and manholes, 1 new conveyor belt press and perform pavement repair and reconnections. Construction shall take place along Town Creek and at the Kendall County WCID #1 wastewater treatment plant in the northeast corner of the intersection of I-10 and RR473.
Kenedy	CD	\$250,000	391	203	51.92	Contractor shall install 2,000 lf of 8" PVC sewer line, 7 manholes, 200 lf of 12" bore with casing and 100 lf of directional bore with appurtenances, and rehabilitate 2 existing manholes. Construction shall take place along Business Highway 181.
Kerens	CD	\$251,820	1,720	1,045	60.76	Contractor shall replace 3075 lf of 6" sewer main along Third and Fourth Avenues and reconstruct 35 manholes throughout the city eliminating inflow and infiltration and raw sewage spills.
Knollwood	CD	\$125,000	375	220	58.67	Contractor shall replace old clay tile sewer lines and brick/mortar manholes. Contractor shall install 3200 l.f. of 6" sewer pipe and 8 manholes. Construction shall take place on Knollwood Drive and the alleys near Valerie Street and Bluffview Drive.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Kosse	CD	\$250,000	524	287	54.77	Contractor shall install 500 GPM booster pump and conduct pipe modifications and electrical upgrades in the Narcissus Water Plant, located along Narcissus Street. Contractor shall install approximately 1,280 linear feet of 6" PVC sewer line, 720 linear feet of 8" PVC line, 1760 LF of 10" PVC line, and nine (9) 4' manholes. Improvements will resolve TECQ violations and significantly reduce health and safety risks.
Kountze	CD	\$250,000	1,996	1,044	52.30	Contractor shall replace 3600 feet of sewer line, install 11 manholes, street repair, and related appurtenances. Construction shall take place on Tubbs and Vanderburg.
La Feria	CD	\$287,597	5,828	3,062	52.54	Contractor shall install 2 new 8" pumps at the wastewater treatment plant and replace deteriorated ductile main with 12" force main made of heavy duty PVC. Force main will run from Lilac Lift Station to the wastewater treatment plant.
La Grange	CD	\$250,000	1,140	771	67.63	Contractor shall replace undersized and deteriorated water lines in the southwest area of town. Construction shall consist of 4,150 LF of 6" and 8" water line, 6 fire hydrants, reconnections, and gate valves. Construction shall take place on Eblin, Live Oak, Cedar, Pecan, Main, and Madison streets.
La Grulla	CD	\$420,000	1,198	940	78.46	Contractor shall make water treatment plant improvements to bring its system into TCEQ standards. Construction shall include the installation of two new 10 ft. diameter metal tanks containing filter media and one raw water pumping station flow distribution header. Construction shall take place at the existing water treatment plant located on Los Alegrias Road.
La Marque	CD	\$350,000	579	354	61.14	Contractor shall address TCEQ and EPA issues by performing sewer system improvements. Construction shall consist of televising, cleaning, and pipebursting 6,590 l.f. of 6" and 8" sewer line and 140 v.f. of manhole rehabilitation. Construction shall take place on Texas Ave, Carolyn St, 1st St, Tallow St, Ave. A, Ave B, 2nd St, and Ave D.
La Salle County	CD	\$262,048	94	92	97.87	Contractor shall rehabilitate the booster station and install 8,600 lf of 6" water main lines throughout Gardendale east of Interstate 35.
Lamesa	CD	\$350,000	1,143	801	70.08	Contractor shall replace undersized water lines and loop approximately 2900 lf of 8" PVC water line, valves and associated service reconnections and install 2 fire hydrants in the South-Central area of Lamesa.
Lawn	CD	\$250,000	360	207	57.50	Contractor shall replace approximately 12,500 linear feet of dilapidated water line to prevent water loss and maintain an adequate residual disinfectant concentration throughout the distribution system, thus resolving a TCEQ enforcement order.
Liberty	CD	\$350,000	5,813	3,075	52.90	Contractor shall replace a lift station to address inflow/infiltration concerns. Construction shall consist of constructing a lift station wet well & control building, 675 lf of 12" sewer line, 2 manholes, and 1,500 lf of 14" force main. Construction shall take place at the lift station south of Washington St on the sewer trunk line to the sewer treatment plant.
Liberty County	CD	\$350,000	621	382	61.51	Contractor shall replace a deteriorated water storage tank. Construction shall consist of installing a 100,000 gallon ground water storage tank, a 10,000 gallon pressure tank, and 2 booster pumps, and constructing a control building with a chlorine system. Construction shall take place on the east side of FM 834 at the current water well.
Linden	CD	\$235,000	61	56	91.80	Contractor shall replace old galvanized steel water pipe through the installation of 4,200 l.f. of 2" and 6" PVC water line and 3 fire hydrants. Contractor shall also provide first-time sewer service to 3 households, and install 800 l.f. of 6" sewer lines and 3 manholes. Construction shall take place on Grubbs, Legion, W. Houston and Walker.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Lockhart	CD	\$250,000	70	64	91.43	Contractor shall replace undersized and deteriorated water lines. Construction shall consist of installing 3,600 LF of 6" PVC water lines, 8 fire hydrants, service connections, street repair, and associated appurtenances. Construction shall take place on Alex, Perez, Church, Locust, West Market, Garcia, and Red River streets.
Lorenzo	CD	\$250,000	149	137	91.95	Contractor shall replace deteriorated water lines and loop the system to improve pressure and ensure a reliable water service. Construction shall include the installation of 4,873 lf of water line, 2 fire hydrants & all necessary appurtenances. Construction shall take place along 5th, 6th, Adams & Washington, Monroe and Jackson.
Lott	CD	\$250,000	751	507	67.51	Contractor shall address TCEQ wastewater treatment plant violations through the installation of one sludge lift station and rehabilitate an existing 20' x 45' sludge drying bed located at the existing wastewater treatment plant on Avenue G.
Lovelady	CD	\$250,000	559	307	54.92	Contractor shall perform water system improvements by constructing a new water well. Construction shall consist of drilling a 300 gpm well, and shall take place on the east side of SH19 adjacent to the city's existing booster plant.
Luling	CD	\$250,000	68	68	100.00	Contractor shall provide first-time public sewer service to 24 households. Construction shall include 6,400 LF of 4" and 6" sewer line, 1 lift station, 8 manholes, 24 first-time connections, mitigate 24 failing septic tanks, and associated appurtenances. Construction shall take place on Austin Street and Brook Road.
Lyford	CD	\$287,597	525	450	85.71	Contractor shall construct a 300 Gallon Per Minute lift station on Glen Lofton Street to increase collection system capacity. Project includes a fiberglass wet well, a valve pit, piping, pumps, electrical controls, generator, and demolition of the older lift station.
Mabank	CD	\$350,000	2,120	1,189	56.08	Contractor shall make WWTP improvements to increase capacity and improve effluent quality to bring the plant into compliance with permit requirements.
Madisonville	CD	\$250,000	4,013	2,056	51.23	Contractor shall replace deteriorated sewer lines and manholes to comply with a TCEQ enforcement order. Construction shall include the installation of 2,905 lf of 6" sewer line, 10 manholes, reconnections, boring, pavement repair and trench safety. Construction shall take place on Madison and E. Limit Streets.
Malakoff	CD	\$250,000	2,070	1,140	55.07	Contractor shall construct a backwash basin pumping station, install 4,500 lf of 4" force main, yard piping within site, and convert 2 off-site pump stations to use alternate chemical disinfection system. Construction shall take place at the existing water treatment plant and from the pump station at water treatment plant to Cedar Creek Reservoir.
Marble Falls	CD	\$250,000	116	87	75.00	Contractor shall replace deteriorated clay and cast iron sewer lines. Construction shall consist of the installation of 3,210 LF of 10" PVC sewer line, 7 manholes, pavement repair, and all associated appurtenances. Construction shall take place on the alleyway between Ave. U and Industrial BLVD, Seventh Street and Fourth Street.
Marfa	CD	\$234,855	161	137	85.09	Contractor shall replace deteriorated sewer collector line with 2677 lf of 8" PVC sewer line a sewer system improvements and install new manholes on the southwest side of the city along Waco, Hoover, Galveston, Yale and Paris Streets.
Marlin	CD	\$250,000	5,897	3,336	56.57	Contractor shall install air release valves and jib crane to pull pumps, replace sump pumps, on site emergency generator with automatic transfer switch and raise upstream manholes. A SCADA system will be installed with a centralized computer at the plant for monitoring.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Martindale	CD	\$250,000	1,012	684	67.59	Contractor shall replace a diesel operated irrigation pump at the city's wastewater treatment plant. Construction shall consist of the installation of a irrigation pump system, demolition and removal of the existing pump station, yard piping, and installion of 3 phase power to the WWTP.
Mason	CD	\$200,000	694	439	63.26	Contractor shall construct a 10" water distribution loop approx 6,600 linear feet long beginning at the intersection of Balsam and Pontotoc Streets.
Mathis	CD	\$300,000	4,997	3,237	64.78	Contractor shall make water system improvements to address TCEQ violations. Construction shall consist of installing 10" raw water line and anchors, a new 400,000 gallon water storage tank, and demolition of existing elevated tank. Construction shall take place at the wastewater treatment plant at Nueces and Fulton Streets.
Memphis	CD	\$250,000	2,410	1,353	56.14	Contractor shall replace deteriorated water mains to ensure a reliable source of water. Construction shall include the installation of 5,320 l.f. of 4", 6", 8" and 10" water line and all necessary appurtenances. Construction shall take place on U.S. Hwy. 287, Medical Drive, 19th Street, Peach Tree Street and 20th Street.
Milford	CD	\$350,000	685	448	65.40	Contractor shall construct a new 100,000 gallon ground storage tank at the site of the existing tank on Water Street and upgrade 1800 LF of old undersized water line on Washington, Hill, Water, and Church streets to provide fire protection and looping of the water system.
Mineola	CD	\$250,000	1,150	783	68.09	Contractor shall demolish approximately 60 dilapidated homes, including cleaning and clearing lots to rid trash and other debris in the South Mineola area.
Moran	CD	\$250,000	232	140	60.34	Contractor shall rehabilitate existing storage tank to bring into TCEQ compliance, which shall include sandblasting and recoating the interior and exterior of the tank, repair the structural damage to the roof of the tank, replace the access hatch, and install a level indicator, ladder safety device and vent.
Murchison	CD	\$250,000	594	342	57.58	Contractor shall make sewer system improvements by rehabilitating a the wastewater treatment plant. Construction shall consist of installing a stationary generator for blower motors, replacing unsafe walkways and stairs, installing a new clarifier motor, and repairing leaking walls. Construction shall take place on the west side of Bankhead St, just north of Little Creek.
Natalia	CD	\$250,000	70	54	77.14	Contractor shall provide first-time public sewer service to 8 households. Construction shall include the installation of 2,735 LF of 8" sewer line, 9 manholes, 8 connections and lift station improvements. Construction shall take place 5th Street and FM 471.
New Summerfield	CD	\$250,000	1,006	625	62.13	Contractor shall make sewer system improvements by installing erosion control measures. Construction shall consist of installing 18,525 lf of 4" channel lock precast concrete blocks and a filter fabric underlayment on side slopes of ponds, earthwork, and appurtenances. Construction shall take place at the wastewater treatment plant on CR 4730 1 mile north of SH 79.
Newcastle	CD	\$250,000	587	502	85.52	Contractor shall rehabilitate the existing water tower and replace the main sewer outfall line to the waste water treatment plant.
Nocona	CD	\$250,000	111	88	79.28	Contractor shall install 7,650 of 6" PVC water line, upgrading existing undersized and deteriorated water mains and install 6 new fire hydrants. Improvements will increase water pressure and flow, and supply improved fire protection to the east central section of the City.
Normangee	CD	\$250,000	716	387	54.05	Contractor shall make wastewater treatment plant improvements to comply with a TCEQ enforcement order. Construction shall include: chlorination equipment, chlorination/control building, chlorine contact basin, piping, valves and electrical controls. Construction shall take place at the existing treatment plant located east of FM 39.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Oak Ridge	CD	\$125,000	201	139	69.15	Contractor shall complete a first-time street paving project on Oak Ridge Drive, Neals Hill Road, and Parkside Lane and shall include scarifying and compacting of existing grade, 4" flexible base with 1-1/2" HMA pavement, on 2,692 l.f. of street reconstruction.
Omaha	CD	\$250,000	1,063	702	66.04	Contractor shall address the city's need to produce an adequate water supply system through the installation of an additional 550 ft. deep water well, test well, submersible pump, fencing, electrical controls and all necessary appurtenances. Well site location shall be on U.S. Hwy. 67.
Orange County	CD	\$250,000	85	85	100.00	Contractor shall replace failing septic systems to 32 low-to-moderate income households in unincorporated areas of Orange County.
Paris	CD	\$250,000	2,308	1,508	65.34	Contractor shall replace old deteriorated sewer mains and manholes in south Paris through the installation of 4,200 l.f. of 8", 10" and 15" sewer main, 7 manholes and all necessary appurtenances. Construction shall take place on Washington, 13th, 6th S.W., Brown and Orange streets.
Perryton	CD	\$250,000	1,147	612	53.36	Contractor shall replace the existing storage tank to address storage and structural problems. Construction shall include the installation of a new 100,000 gallon elevated storage tank, concrete foundation, painting, electrical, removal of existing tank and all necessary appurtenances. Construction shall take place on Amherst and Santa Fe.
Pilot Point	CD	\$350,000	3,430	1,751	51.05	Contractor shall reconstruct an elevated water storage tank on Prairie Street and a ground water storage tank on North Side Drive, conduct waterworks and SCADA improvements at a plant on Division Street, and add 6 new taps and valves along the city's 10" supply main using 120 LF of 10" main and 120 LF of 6" main on Prairie and Division streets.
Pinehurst	CD	\$250,000	536	402	75.00	Contractor shall replace deteriorated sewer yard lines and brick manholes. Contractor shall install 1900 lf of 8" pipeburst, 2 manholes, related appurtenances and street repair on Nightingale Street.
Port Isabel	CD	\$287,597	4,865	3,028	62.24	Contractor shall install 3 fire hydrants on Garcia and Hickman Streets and South Shore Drive and reconstruct the deteriorated paved streets of Cisneros Street from Adams Street to West Shore Drive and Harrison Street from Musina Street to Longoria Street.
Port Lavaca	CD	\$250,000	92	73	79.35	Contractor shall make water system improvements by replacing deteriorated water lines. Construction shall consist of installing 2,800 lf of water mains, sidewalks, reconnections, and pavement repair. Construction shall take place in the George Adams Park area.
Port Neches	CD	\$250,000	297	152	51.18	Contractor shall replace deteriorated sewer collection system with 1790 lf of 12" PVC sewer line, 9 manholes, 10 sewer street crossings and service reconnections in the East Port Neches Neighborhood.
Post	CD	\$250,000	2,274	1,345	59.15	Contractor shall drill 3 new water wells to provide an alternative water source for the city. Construction shall take place on the east side of US HWY 84, south of the town of Southland.
Pottsboro	CD	\$125,000	192	161	83.85	Contractor shall replace deteriorating 6" cast iron water pipe with 3,790 l.f. of 6" PVC water pipe along the 100 & 200 blocks of Franklin Street, Houston Street, Magnolia Street, Williams Street, and the 300 block of Thompson Street.
Presidio	CD	\$234,859	361	300	83.10	Contractor shall provide flood and drainage improvements. Construction shall include inlet improvements, channel excavation, construction of new concrete channels with box culverts and headwalls at O'Reilly Street and Rio Grand Ave.
Raymondville	CD	\$287,597	8,628	5,564	64.49	Contractor shall replace undersized water and sewer force main lines, located on Sauza and 10th Streets, and 6th and 11th Streets, respectively, to increase capacity to meet TCEQ requirements.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Redwater	CD	\$250,000	59	36	61.02	Contractor shall provide first-time sewer service to 20 households in northwest Redwater through the installation of 2,900 l.f. of 8" sewer main, 2,000 l.f. of 3" force main, 9 manholes, one sewer lift station, portable generator and abandonment of existing septic tanks.
Reno	CD	\$350,000	2,460	2,394	97.32	Contractor shall drill a new well located on Rhonda B. Road and rehab an existing ground water storage tank and service pumps and relocate it to a site adjacent to the Springtown transmission main, increasing the water supply for the city.
Rio Grande City	CD	\$420,000	265	239	90.19	Contractor shall construct approximately 6,749 lf of street improvements. Construction shall take place at the following locations: Kennedy, Pine, Redwood, and Escobedo.
Rio Hondo	CD	\$287,597	1,884	1,019	54.09	Contractor shall replace an undersized, sub-standard sewer collector line, located on Reynolds Street, with a new 18" PVC line, install 3 manholes, and one (1) electrical panel.
Robert Lee	CD	\$200,000	1,056	628	59.47	Contractor shall make water system improvements to comply with a TCEQ Agreed Order. Construction shall consist of replacing 2 filter medias, replacing the main water supply line, and related appurtenances. Construction shall take place at the water treatment plant located in the northeastern part of town and the elevated storage tank on 15th street.
Robstown	CD	\$300,000	7,203	4,785	66.43	Contractor shall replace 5,000 lf of 14" PVC force main, 150 lf of bore and case force main, 4 air release valves, and pavement repair along George Avenue and Ruben Chavez Road.
Roby	CD	\$250,000	442	252	57.01	Contractor shall construct a new water well to supplement the treated water they receive from the City of Sweetwater. Project shall include acquisition of 25 acres of land at approximately \$2,500 per acre.
Rochester	CD	\$250,000	357	212	59.38	Contractor shall redesign, construct and repermit the waste water treatment facility to address TCEQ Enforcement Order. Construction shall include the installation of monitoring wells, one new lift station, receiving pond, new package plant and all necessary appurtenances. Construction shall take place off of the Santa Fe Railroad and State Highway 283.
Rockdale	CD	\$250,000	3,229	1,649	51.07	Contractor shall address inflow and infiltration concerns by replacing deteriorated sewer lines in the eastern half of the city. Construction shall consist of installing 21,500 lf of 10" and 12" sewer line, 9 manholes, and associated appurtenances in the eastern side of the city.
Rocksprings	CD	\$219,984	1,324	859	64.88	Contractor shall install 166 lf of 6" water main line and 316 lf of 8" & 6" water main line at the Rocksprings Wastewater Facility and make improvements to the water system on Main Street, Old Del Rio Road, Wilson Street, Highway 55, and College Street.
Rogers	CD	\$250,000	1,193	623	52.22	The city will address a TCEQ Agreed Order by replacing deteriorated sewer main lines and manholes. Contractor shall install approximately 2,500 lf of sewer line, 7 manholes, and necessary appurtenances. Construction shall take place in the central and north sections of the city.
Roma	CD	\$420,000	9,852	7,405	75.16	Contractor shall construct a new 60 x 100ft steel fire protection facility with a rated wind load of approximately 125 mpr. Construction shall consist of building a 6,371 sq. ft. fire station to be located on US Hwy 83.
Runge	CD	\$250,000	1,104	719	65.13	Contractor shall install 2,000 lf of 8" sewer line, 1,225 sy of flexible base/pavement, 2,000 lf of trench safety, 5 manholes, 4 manhole improvements, 10 cy of concrete encasement/saddle, traffic controls and bypass pumping. Construction shall take place on Victoria, Aransas, Refugio, Front, and Mugge streets.
Sabinal	CD	\$228,994	72	58	80.56	Contractor shall upgrade sewer lines on Houston Street with 870 lf of 8" & 6" sewer & service lines, connect 1 household to sewer, and perform paving work on El Paso Street and Cullins Ave.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
San Augustine	CD	\$250,000	1,536	818	53.26	Contractor shall replace the Montgomery Street and MLK lift stations and decommission the Richey Loop lift station. Construction shall consist of installing 892 LF of 18" and 6" sewer main and installing and rehabilitating manholes. Construction shall take place cross country from Richey Street to Holman Street.
Santa Anna	CD	\$250,000	1,009	705	69.87	Contractor shall perform water system improvements to address TCEQ violations and meet water storage needs. Construction shall consist of demolishing a 500,000 gal. ground elevated tank and replacing it with a new 100,000 gal. tank. Construction shall take place northeast of the city limits, east of FM 1176 and north of US Highways 84/86.
Santa Rosa	CD	\$287,597	2,866	1,823	63.61	Contractor shall reconstruct 4 dilapidated streets (3rd Street, Las Flores Street, Jose R. Cruz Street, and N. Louisiana Street), and purchase a brush fire truck.
Seven Points	CD	\$250,000	98	57	58.16	Contractor shall purchase approximately 99 cy of aggregate, 7,000 lbs of CRS-2P emulsion, and 20,800 sy of 6" cement base to repair roads at Mason Drive, Scaramento, Taylor, Clay, and Pine Street; work shall be performed through an interlocal agreement with Henderson County.
Shiner	CD	\$250,000	38	28	73.68	Contractor shall provide first-time sewer service to 18 households. Construction shall consist of acquiring a privately owned lift station, installing 2,825 lf of 8" sewer line, manholes, 1,475 lf 3" force main, abandonment of septic systems, and appurtenances. Construction shall take place in the ETJ northeast of the city.
Sinton	CD	\$300,000	463	333	71.92	Contractor shall address overloaded collector lines by rerouting sewer line and enlarging the Pirate lift station. Contractor shall install 5,900 lf of 8" force main, 300 lf of bore and cased force main, upgrade the Pirage lift station, and related appurtenances. Construction shall take place in the Rancho Chico colonia area.
Slaton	CD	\$250,000	2,366	1,747	73.84	Contractor shall rehabilitate pump station #4 to ensure an adequate water supply. Construction shall include the installation of 3 new pumps, piping, valves, metering equipment, controls, chlorination system and electrical. Construction shall take place at 5th Street & Murray Avenue.
Smithville	CD	\$250,000	1,379	1,072	77.74	Contractor shall replace 2 lift stations by installing 2 new lift stations, 3,700 LF of 8" sewer main, and railroad boring. Construction shall take place along Martin Luther King, Taylor, North 1st Street, Garwood and North 2nd Street.
Socorro	CD	\$234,859	145	121	83.45	Contractor shall provide street improvements in the Lynn Park subdivision. Construction shall take place on Donna Maria Drive from Horizon Boulevard. to Wilton Place.
Sonora	CD	\$200,000	198	123	62.12	Contractor shall perform sewer system improvements to meet minimum TCEQ standards. Construction shall consist of replacing 4,280 l.f. of 6" PVC line and 15 manholes. Construction shall take place on North Crockett Ave, West 4th Street, Tom Green Ave, West 3rd St, and West 2nd St.
Spearman	CD	\$250,000	574	541	94.25	Contractor shall replace the existing lift station in the northeastern portion of the city to improve capacity. Construction shall include the installation of a new lift station, 2,300 l.f. of 12" gravity flow sewer line, 8 manholes, electrical services and all necessary appurtenances.
Stephenville	CD	\$350,000	38	24	63.16	Contractor shall extend sewer mains to service first-time sewer connections to 20 households on College Farm Road on the northeast side of town.
Sudan	CD	\$250,000	953	508	53.31	Contractor shall replace undersized deteriorated water lines and loop the system to improve pressure and quality. Construction shall include the installation of 5,450 l.f. 6" water line, flush valves, looping and 4 fire hydrants. Construction shall take place on Commerce, Furneaux, Wilson, Boeson, Ormand, Hay and Nelson.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Talco	CD	\$250,000	533	330	61.91	Contractor shall address lack of adequate production of usable water due to only one functional water well. Construction shall include a new 550 ft. water well, test well, submersible pump, 200 l.f. of 8" PVC water line, sterilization and testing and all necessary appurtenances. The well site shall take place next to the existing well #3.
Tatum	CD	\$250,000	668	369	55.24	Contractor shall install approx 1,750 lf of 8" PVC sewer main, 1,500 lf of 6" PVC sewer main, and replace 12 manholes and associated appurtenances. Construction shall take place on Jefferson (Loop 43), north of FM 1797, Beauregard St, and Johnson St.
Teague	CD	\$250,000	1,581	924	58.44	Contractor shall complete improvements to pump system, electrical components, site piping/valves, sludge drying bed improvements and Imhoff tank improvements at the West Wastewater Treatment Plant. Improvements will address TCEQ violations.
Tye	CD	\$250,000	147	96	65.31	Contractor shall install approximately 6,300 linear feet of 6" sewer line, 2,500 linear feet of 6" pressure line, 5,150 linear feet of 4" service line, 12 manholes, one lift station and 56 service connections to provide first time sewer service.
Uvalde	CD	\$228,995	145	98	67.59	Contractor shall replace 2,750 lf of old & substandard water lines with new 6" diameter mains and install new fittings, valves and fire hydrants on West Nueces Street, West Frio Street, Commerce Street, MacKenzie Street, and Bowie Street.
Valentine	CD	\$234,859	152	122	80.26	Contractor shall provide sewer system improvements for the city. Construction shall include 3,180 lf of 2" sewer line and a lift station in the west part of the city.
Walker County	CD	\$350,000	560	322	57.50	Contractor shall, on behalf of Walker County S.U.D., perform water system improvements to address TCEQ violations. Construction shall consist of installing a 150,000 gallon elevated water storage tank and 11,500 l.f. of 4" and 2" water line. Construction shall take place in the Lake Falls Estates at the end of Lake Falls Rd. and along FM 2628.
Waskom	CD	\$250,000	1,977	1,015	51.34	Contractor shall drill a 100 GPM well on an acquired site, install 4,000 LF of 4" raw water line and valves, and tie into an existing raw water main. Construction shall take place on Mary Elizabeth Road in northern Waskom.
West Orange	CD	\$250,000	172	172	100.00	Contractor shall replace deteriorated sewer service yard lines and install two clean outs for 70 low-to-moderate households. Households are located citywide.
Whitesboro	CD	\$125,000	53	37	69.81	Contractor shall pave along the 400,500 and 600 blocks of Water Street to include excavation, grading, laying and compacting base material, and resurfacing of roadway.
Wickett	CD	\$350,000	429	220	51.28	Contractor shall drill a well to ensure adequate water supply for the community. Construction shall take place on El Paso Avenue.
Windom	CD	\$125,000	231	151	65.37	Contractor shall construct the following sewer treatment plant improvements: excavation for lagoon, embankment, site work, and yard piping. Construction shall take place on the east side of city near FM 1743.
Winfield	CD	\$250,000	75	75	100.00	Contractor shall replace dilapidated water lines through the installation of 3,505 l.f. of 3" and 6" PVC water line, asphalt repair, water line connections and all necessary appurtenances. Construction shall take place on Second, Fifth, Miller and Cleveland streets and along U.S. Hwy. 67.
Winters	CD	\$250,000	2,953	1,520	51.47	Contractor shall reconstruct a lift station, associated appurtenances, and intruder-resistant fencing around the facility to improve the pumping capacity with a triplex pump configuration meeting TCEQ's minimum pumping requirements.

**Texas Community Development Block Grant Program (TxCDBG)
2009 Community Development Fund Awards**

Grantee	Fund	TxCDBG Funded Amount	Total Persons Benefit	Total Low/Mod Benefit	% of Low/Mod	Project Description
Wise County	CD	\$259,000	52	41	78.85	Contractor shall assist Walnut Creek SUD to provide 1st-time water service to 17 HH along County Road 3592.
Zavalla	CD	\$250,000	647	386	59.66	Contractor shall install 6,960 lf of 3", 4", and 6" water lines, 2 highway crossings by boring and casing, related appurtenances, and reconnections for existing customers. Construction shall take place on US69 North, Railroad Street, and US69 South.
Total Count:	173	\$46,280,195				

Source: Office of Rural Community Affairs